BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

NO:BBMP/EE/YNK.D/EPMT-15/2019-20 Dt:13-1-2020

APPROVED TENDER SCHEDULE –'B'

Package-5

Name of Work :-Improvements and developments of roads and drains at yelahanka 4th phase and construction of providing parking lot at 16th A Main, A sector, 16th B in yelahanka satellite town sub division (PACKAGE - 05)

Sl	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Sri.B B UMESHA	
				Rate	Rate in Words
1	Removing and resetting of footpath slab	Sqm	288.00	219.26	Two Hundred Nineteen Paise TwentySix Only
2	Removing and resetting of kerb stones	M	320.00	110.19	One Hundred Ten Paise Nineteen Only
3	Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specificationsand as per directoins of the Engineer in charge of work.	Cum	1156.40	222.38	Two Hundred TwentyTwo Paise ThirtyEight Only
4	KSRB 4-1.2 : Providing and laying in position plain cement concrete Cum of Mix 1:3:6 with OPC @ 220kgs, with 40mm anddown size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed machine mixed concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials labour HOM curing complete as per specifications. Specification No. KBS 4.1 4.2	Cum	180.75	5780.92	Five Thousand Seven Hundred Eighty Paise NinetyTwo Only

	oviding TMT Bars Fe 500 steel einforcement for R.C.C. work including straightening, cutting, bending, hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per disign (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specification and as per directoins of the Engineer in charge of work.	T	26.64	75943.33	SeventyFive Thousand Nine Hundred FourtyThree Paise ThirtyThree Only
6	Providing and laying plain/reinforced cement concrete for side drains Wall & bottom thickness 15cm using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500,1700, 2200. including cost of materials, labour, HOM complete as per specifications.	Cum	442.08	7423.71	Seven Thousand Four Hundred TwentyThree Paise SeventyOne Only
7	Supplying and fixing precast reinforced concrete slab 10 cm thick of mix M20 using 20mm and downsize graded granite metal using reinforcement 10mm dia steel at 150mm C/c both ways cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface etc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of cost of all materials(data Rate enclosed)	sqm	777.60	2453.85	Two Thousand Four Hundred FiftyThree Paise EightyFive Only
8	Providing and laying Pre Cast Drain Cover slabs of 250mm thick of mix M20 using graded granite jelly 20mm down size with steel reinforcement, including from work, lift charges, curing and concrete finished surfaces on both side etc. complete and as per drawing and direction of Engineer-in-charge of work (data Rate enclosed)	Sqm	7.20	5688.90	Five Thousand Six Hundred EightyEight Paise Ninety Only

	roviding and fixing Pre cast solid concrete erb stones of size 450 x 200 x 400 mm made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting etc., complete as per specifications and as per directions of Engineer in charge of work.	Nos	1200.00	500.85	Five Hundred Paise EightyFive Only
10	Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications and as per directoins of the Engineer in charge of work.	Sqm	360.00	89.04	EightyNine Paise Four Only
11	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.43cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications and directions of the Engineer in charge.	Cum	14.74	5930.06	Five Thousand Nine Hundred Thirty Paise Six Only
12	Providing and laying M-15 cement concrete flooring 60 mm thick with metallic concrete hardner toping, under layer of 45mm thick M-15 cement concrete using broken granite metal of 20mm and down size and top layer of 15mm thick metallic cement hardner consisting of mix 1:2 (1 cement hardner mix : 2 granite metal 10mm nominal size) by volume, with metalic hardening compound of approved quality mix in the ratio of 4:1 (4 part of cement = 1 part of metallic floor hardening compound of approved quality by wt) , including finishing, cost of materials, labour, curing, complete as per specifications and directions of the Engineer in charge	sqm	2337.02	780.21	Seven Hundred Eighty Paise TwentyOne Only

	Fabricating providing and erecting in position of MS Hot Dip galvanized sq hallow poles of 132 x132 heavy gauge length 3000mm with MS Hot Dip galvanized grill work as per approved design and drawing of chief architect using 12 x75mm galvanized flat for alround frame and 20 x 20mm galvanized forged ornamental arrow head in top and buttom the work is inclusive of throughing flat square rods placing welding all the joints including griding finishing 2 coats of anticorrossive paint over one coat of metal primer the rate is inclusive of all materials all items of work cost painting welding cutting griding with lead and lift as per specifications including loading and unloading with cost and conveyance of all materials labour machinery and incidental charges for the successful completion of the work as per direction of engineer in charge of work.	sqm	490.00	9601.35	Nine Thousand Six Hundred One Paise ThirtyFive Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.